SHIMOGA DIVISION.

ADVERTISEMENT.

The 28th October 1889.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 15th November 1889, for restoring Rubbligere Tank, Registered No. 150, Sorab Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th May 1891.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Shimoga between the hours of 11 A. M. and 5 P. M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed, or should specify ( ) per cent less than estimated rates.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for restoring Rubbligere Tank, Registered No. 150, Sorab Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of Work.	Unit of Work.	Rate.	Remarks.
Bund—			
Earthwork	C. Yd.	4,540	
Turfing	Sq.	248·16	
Clearing shrub jungle	..	L. S.	
Bench mark stone	No.	2	
Grade stone	do	48	
Tank register stone	do	1	
Gauge stone	do	1	
Stone work	C. Yd.	2,421	
Constructing 3 sluices—			
Brick in surki mortar	C. Ft.	3,807	
Plastering	Sq.	7·00	
Stone slabs	S. Ft.	520	
Do	Do	311	
Gibbet and orfied stones	..	L. S.	
Date stones	No.	3	
Constructing 3 W. Weirs 25, 50, & 70 feet—			
Excavation	..	L. S.	
Brick in surki mortar	C. Ft.	5,204	
Plastering	Sq.	13·60	
Rough stone work	C. Yd.	575	
Stone slabs	S. Ft.	414	
Do	Do	112	
Date stone	No.	3	
Grading & improving channel	L. S.		

A. S. NAGAVKAR,
Executive Engineer.